

September, 14, 2018

Town Of Yorktown:

Removal of structures on 9218 and 9300 W Canal St.

- Deconstruction in their entirety
- All wood, insulation, roofing, etc. will be placed in dumpsters and taken to landfill
- Concrete, brick, clock, asphalt, foundations, soil, rock, stone etc. will be recycled or dumped at hard fill site.
- Gas, electric, water, and phone lines are towns responsibility to disconnect
- Sanitary laterals will be exposed and capped with locations recorded and inspected by waste water official.
- After site inspection, site to receive 6" #53 stone graded and compacted
- Upon notice to proceed all contents attached or unattached become contractors property

Scott M& Kable

Material, Equipment and Labor

\$57,500