



**Walnut Street
Sanitary Sewer
Proposal**

Attn: **Peter L. Olson, Town Manager**
polson@yorktownindiana.org
Tim Caldwell, Department of Street
tcaldewll@yorktownindiana.org
PO Box 518 Yorktown, IN 47396
Physical Address 2400 S Russ St Yorktown, IN 47396

LTB Construction, Inc. is pleased to submit the following proposal for the referenced project. This Proposal and these Prices are based upon items listed below:

Scope:

- Sanitary Sewer Structure Installation
- Center line of new sanitary line to remain within right-of-way 15 to 18 feet behind existing concrete curb line
- 180'-0" of 8 inch gasketed SDR 35 Sewer Pipe
- Three (3) 6 inch 8"x6" taps with 10'-0" extension for individual lot connections
- One (1) 8-inch 20-foot extension south of southern most tap with riser and cleanout connection
- New sanitary sewer structure to be cored and will have a poured flowline
- Existing sanitary structure to be cored to receive new sanitary sewer line
- 4% minimum grade from southern most start to existing sanitary structure
- Granular materials (#8 stone) 8 inch below flowline and 12 inch above, soil backfill to surface elevation
- Street and concrete curb/walk cuts
- Concrete placement for curb/walks as well as within 2" of asphalt service in roadway
- Asphalt patch as required upon completion of sanitary sewer line

Mobilization:

- Delivery of excavation equipment
- Delivery of structure, pipe, and associated accessories to complete the task
- Delivery of granular materials
- Trucking for excess soils
- Coordination of traffic control devices with the Street Department

Street Cut:

- Saw cut street and concrete curb that will be damaged during sanitary sewer installation



**Walnut Street
Sanitary Sewer
Proposal**

Excavation:

- Pothole existing storm structure and storm piping from north to south
- Site layout for sanitary sewer and lateral taps
- Excavate from south to north at a 4% grade minimum
- Provide concrete structure with risers, gasket materials, grate, and concrete core/concrete flow line
- Provide 8" sanitary SDR 35 gasketed piping and associated accessories
- Provide granular backfill and cover
- Provide soil backfill to surface elevation, mounding for settling
- Remove all other remaining excavated soils off site
- Concrete placement on curbs and road cuts
- Asphalt placement on road cuts

Exclusions & Clarification:

- LTB Construction Inc shall coordinate public locates within the areas of excavation
- Work to be completed during normal business hours
- LTB and the Town Street Department to work together for traffic control devices and traffic shifts during this activity
- Price based on direction and site investigation, slight design change from original site review. LTB has changed the direction and has added a concrete structure to mitigate issues with the exiting storm pipe crossing.
- Price good for 30 days from the date of Dec. 8th, 2021.

Total for complete Project

\$54,965.00

If you have any questions please call,

Dane Carpenter

Mobile (317) 710-8259