

VERN'S CONCRETE

912 East 53rd St Suite B
Anderson, IN 46013

Estimate

Date	Estimate #
5/9/2024	1195

Name / Address
Yorktown Marrows Meadow Chase Bruton 1901 S Tiger Dr Yorktown, IN 47396

Project

Description	Qty	Rate	Total
<p>110'x65' Concrete slab for basketball court poured at 4" thick Fiber mesh Reinforcement, 2" stone compacted 5'x20' foot access walk to court Construction of basketball court slab, side walk, installation of basketball goals provided by owners. ***Any additional protection from weather will be an extra charge*** ***\$30.00 per blanket, \$95.00 per man hour to apply and collect said protection (Approx \$3000.00)***</p> <p>Form and pour concrete to dimensions listed above. Establish and compact new sub grade with # 53 stone. Pour 6 bag concrete with fiber mesh reinforcement-apply standard finish. Exterior will be stone Form and pour concrete to dimensions listed above. Establish and compact new sub grade with #53 mix, interior will be gravel mix. Install control joints where needed. Apply: surface aid/hardener to concrete surface, apply sealer. All labor, material, and equipment included in price. 1/2 down, balance due upon completion. Insurance and references available upon request.</p> <p>If there are any unforeseen circumstances that were not visible at the time of estimate, this will be brought to the owner's attention immediately. Payment will be subject to any additions or deductions in accordance with any mutually agreed to and signed upon changes and/or modifications in the work.</p>		64,995.00	64,995.00
		Total	