



**Town of Yorktown  
Asphalt Patching  
Yorktown Middle School**

Attn: **Pete Olson**  
**9312 W Smith St.**  
**Yorktown, IN 47396**  
[polson@yorktownindiana.org](mailto:polson@yorktownindiana.org)  
(765)-273-0799

LTB Construction, Inc. is pleased to submit the following proposals for the referenced project sites. The area to be repaired is in the main drive of the Yorktown Middle School. The patching is a result of a water main break and repairs.

**Mobilization/Prep:**

- All equipment, materials (asphalt/tac) manpower will be mobilized onsite to complete the necessary patch as indicated on our site visit on Oct. 11, 2021. Approximately 2100 square foot of areas to be patched.
- We shall loan to the Town of Yorktown two (2) 1/2" steel plates to allow for vehicular passage prior to asphalt placement

**Tac:**

- We shall provide tac coat to all edges prior to installation of HMA Intermediate/Surface course

**Binder:**

- We shall provide and place an average depth of 3 1/2" of HMA Intermediate layer and compact

**Surface:**

- We shall provide and place an average depth of 1 1/2" HMA Surface layer and compact



**Town of Yorktown  
Asphalt Patching  
Yorktown Middle School**

Attn: **Pete Olson**  
**9312 W Smith St.**  
**Yorktown, IN 47396**  
[polson@yorktownindiana.org](mailto:polson@yorktownindiana.org)  
**(765)-273-0799**

**Exclusions and Clarifications**

- All areas shall be prepared by Others
- All granular materials shall be compacted by Others
- All traffic barricades shall be provided by Others
- Work to be completed during normal business hours

<b>Total</b>	<b><u>\$23,940.00</u></b>
--------------	---------------------------

If you have any questions please call,

Dane Carpenter

Mobile (317) 710-8259