

**Indianapolis Branch**

3451 Developers Road

Indianapolis, IN 46227

Ph: 317-783-5434

Fax: 317-783-5870

To: Estimator	Quotation #:	JG08222022-7
	Date:	08/22/2022
	Ref:	Yorktown Water Well #13

Recommend

We are pleased to quote the following new equipment for your consideration:

Quantity 1 - Generac Industrial diesel engine-driven generator set with turbocharged/aftercooled 6-cylinder 6.7L engine, consisting of the following features and accessories:

- Stationary Emergency-Standby rated
- 150 kW Rating, wired for 120/240 VAC three phase, 60 Hz
- Permanent Magnet Excitation
- Level 1 Acoustic Enclosure, Steel
 - Industrial Grey Baked-On Powder Coat Finish
- UL2200
- EPA Certified
- H-100 Control Panel
 - Meets NFPA 99 and 110 requirements
 - Temp Range -40 to 70 degrees C
 - Digital Microprocessor:
 - Two 4-line x 20 displays, full system status
 - 3 Phase sensing, +/-0.25% digital voltage regulation
 - RS232, RS485 and Canbus remote ports
 - Waterproof connections
 - All engine sensors are 4-20ma for minimal interference
 - Programmable I/O
 - Built-in PLC for special applications
 - Engine function monitoring and control:
 - Full range standby operation; programmable auto crank, Emergency Stop, Auto-Off-Manual switch
 - Isochronous Governor, +/-0.25% frequency regulation
 - Full system status on all AC output and engine function parameters
 - Service reminders, trending, fault history (alarm log)
 - I2T function for full generator protection
 - Selectable low-speed exercise
 - 2-wire start controls for any 2-wire transfer switch

- Battery Charger, 10 Amp, NFPA 110 compliant, installed
- Coolant Heater, 1500W
- 24" 322 Gallon Double-Wall UL142 Basetank
 - Mechanical fuel level indicator gauge
 - Electronic fuel level sender
 - Emergency Vent
 - 8" Fuel Fill Extension
- 3 Owner's Manuals
- 120V GFCI and 240V Outlet
- MLCB, 100% rated thermal-magnetic
 - 300 Amp
- Standard 2-Year Limited Warranty
- SD0150JG176.7D18HPSY3

Quantity 1 – Automatic Transfer Switch

- 300 Amp
- 3 pole, 120/240 VAC three phase
- NEMA 3R Enclosure
- Service Entrance Rated
- In Phase Only Transfer
- Standard two year basic warranty

TOTAL NET PRICE: \$ 56,005.00

Price Includes:

- 1) Prints, drawings and manuals
- 2) Battery, Oil, and Antifreeze
- 3) Freight Allowed-FOB: Factory, unloaded by others
- 4) Start up, Test, and Training after Installation
 - * Start Up covers One Day (1) on site during normal business hours.
 - If additional trips or time is required for reasons beyond our scope, then additional charges may apply.

Notes:

- 1) Applicable Taxes NOT Included
- 2) Installation NOT Included
- 3) Fuel NOT Included
- 4) Shipment: 26-30 Weeks After Receipt of Order
- 5) Terms: Net 30 Days With Approved Credit
- 6) Additional 3% fee on any Credit Card Payments.
- 7) Price valid for 30 days

Jacob Giesman

**Indianapolis Branch**

3451 Developers Road

Indianapolis, IN 46227

Ph: 317-783-5434

Fax: 317-783-5870

To:	Estimator	Quotation #:	JG08222022-6
		Date:	08/22/2022
		Ref:	Yorktown Water Well #23

We are pleased to quote the following new equipment for your consideration:

Quantity 1 - Generac Industrial diesel engine-driven generator set with turbocharged/aftercooled 6-cylinder 6.7L engine, consisting of the following features and accessories:

- Stationary Emergency-Standby rated
- 130 kW Rating, wired for 120/240 VAC three phase, 60 Hz
- Brushless Excitation
- Level 1 Acoustic Enclosure, Steel
 - Industrial Grey Baked-On Powder Coat Finish
- UL2200
- EPA Certified
- H-100 Control Panel
 - Meets NFPA 99 and 110 requirements
 - Temp Range -40 to 70 degrees C
 - Digital Microprocessor:
 - Two 4-line x 20 displays, full system status
 - 3 Phase sensing, +/-0.25% digital voltage regulation
 - RS232, RS485 and Canbus remote ports
 - Waterproof connections
 - All engine sensors are 4-20ma for minimal interference
 - Programmable I/O
 - Built-in PLC for special applications
 - Engine function monitoring and control:
 - Full range standby operation; programmable auto crank, Emergency Stop, Auto-Off-Manual switch
 - Isochronous Governor, +/-0.25% frequency regulation
 - Full system status on all AC output and engine function parameters
 - Service reminders, trending, fault history (alarm log)
 - I2T function for full generator protection
 - Selectable low-speed exercise
 - 2-wire start controls for any 2-wire transfer switch

- Battery Charger, 10 Amp, NFPA 110 compliant, installed
- Coolant Heater, 1500W
- 24" 220 Gallon Double-Wall UL142 Basetank
 - Mechanical fuel level indicator gauge
 - Electronic fuel level sender
 - Emergency Vent
 - 8" Fuel Fill Extension
- 3 Owner's Manuals
- 120V GFCI and 240V Outlet
- MLCB, 100% rated thermal-magnetic
 - 300 Amp
- Standard 2-Year Limited Warranty
- SD0130JG176.7D18HBSY3

Quantity 1 – Automatic Transfer Switch

- 300 Amp
- 3 pole, 120/240 VAC three phase
- NEMA 3R Enclosure
- Service Entrance Rated
- In Phase Only Transfer
- Standard two year basic warranty

TOTAL NET PRICE: \$ 53,365.00

Price Includes:

- 1) Prints, drawings and manuals
- 2) Battery, Oil, and Antifreeze
- 3) Freight Allowed-FOB: Factory, unloaded by others
- 4) Start up, Test, and Training after Installation
 - * Start Up covers One Day (1) on site during normal business hours.
 - If additional trips or time is required for reasons beyond our scope, then additional charges may apply.

Notes:

- 1) Applicable Taxes NOT Included
- 2) Installation NOT Included
- 3) Fuel NOT Included
- 4) Shipment: 26-30 Weeks After Receipt of Order
- 5) Terms: Net 30 Days With Approved Credit
- 6) Additional 3% fee on any Credit Card Payments.
- 7) Price valid for 30 days

Jacob Giesman