



## Quote and Scope of Work

Town of Yorktown  
Butler Fairman & Seufert, Inc.  
8450 Westfield Blvd. Suite 300  
Indianapolis, IN 46240  
Attn: Matt Spidel

August 29, 2019  
Park One North Utility Extension

For installation of approximately 180' of 2" poly pipe from the existing manhole, through the existing 16" casing pipe, installing a new manhole structure with sanitary lid, and installing an air release valve. Adding spacers around the 2" pipe within the casing pipe and installing end caps on the casing pipe. Core drilling the 2 manholes and installing core boots. Bedding the pipe and new structure in #8 stone, adding tracer wire, and backfilling with existing dirt on site. Hauling off spoils.

**Total \$17,150.00**

For extending the existing water line including adding an 8" cross, adding 2-8" valves and extending the pipe parallel with the road 20' in each direction and capping off each lateral. Adding an 8x6 reducer, 6" valve and 6" fire hydrant with Stortz connection on the north side of the cross. Bedding the pipe with sand, adding tracer wire and backfilling with existing dirt on site. Adding bacteria testing.

**Total \$18,280.00**

### Alternate 1

For installation of approximately 180' of 8" C900 sanitary pipe from the existing manhole, through the existing 16" casing pipe, installing a new manhole structure with sanitary lid. Adding spacers around the 8" pipe within the casing pipe and installing end caps on the casing pipe. Core drilling the 2 manholes and installing core boots. Bedding the pipe and new structure in #8 stone, adding tracer wire, and backfilling with existing dirt on site. Hauling off spoils.

**Total \$13,180.00**

### Excluded:

- All permits, easements, inspection, layouts, compaction testing, and/or engineering fees.
- Prevailing wage and taxes
- No asphalt or concrete installation, repair, or replace other than noted
- Underground utilities, conduits, foundations, pilings, or other structures not noted that are encountered will be removed at an additional expense.
- Hazardous materials encountered will be removed & disposal of at the expense of others.
- Landscaping including finish grade, grass seed, and straw
- Light pole or base removal
- Road cut concrete or asphalt
- Underslab, concrete, or asphalt stone or grading
- Top soil importing.
- Dewatering wells
- Street traffic control
- Repair and/or replace concrete curbs, sidewalks, asphalt street and landscaping

If you have any questions please call.

*Andy DeLucio*

Andy DeLucio, Project Manager/Estimator  
Culy Contracting, Inc.

With signature below the quote is accepted in said amount above \_\_\_\_\_

Printed Name

Title

Signature

Date

