



ESTIMATE

Prepared for:

Nick Shirk
8905 W Smith St
Yorktown, IN 47396
nickshirk50@yahoo.com
(765) 729-7680

September 8, 2022

No. 1810

AdPro Construction And Concrete Coatings
13281 W State Rd 32, Yorktown, IN 47396
P: (765) 283-2965 | david@adpro-cc.com

Fire Dept.

Scope of Work

Total

Evolution Chip System-Front

\$10,524.33

Evolution Chip System Scope of Work

1. Preparation of Area - Preparation includes diamond grinding of all surface area. Dust is minimized by having all grinders hooked up to vacuum systems.
2. Concrete reconstruction - Penntek menders and fillers are used to fix pits and cracks before the process begins.
3. Vac Floor clean
4. Basecoat - XP 275 - Polyurea Basecoat - Penntek's 100% solids, self-priming, pure polyuria base coat is mixed and applied
5. Broadcasting the chip system - Immediately, after the base coat application, the chip is generously broadcast by hand, providing both color and texture to the floor.
6. Scraping the chip system - Once the base coat is fully cured the floor is scraped and vacuumed to remove any loose or vertical standing chips.
7. Clear Coat - NX 300 - The final step is to roll the UV stable polyaspartic clear coat.
8. Leave project broom clean

Evolution Chip System-back

\$15,744.37

Evolution Chip System Scope of Work

1. Preparation of Area - Preparation includes diamond grinding of all surface area. Dust is minimized by having all grinders hooked up to vacuum systems.
2. Concrete reconstruction - Penntek menders and fillers are used to fix pits and cracks before the process begins.
3. Vac Floor clean
4. Basecoat - XP 275 - Polyurea Basecoat - Penntek's 100% solids, self-priming, pure polyuria base coat is mixed and applied
5. Broadcasting the chip system - Immediately, after the base coat application, the chip is generously broadcast by hand, providing both color and texture to the floor.
6. Scraping the chip system - Once the base coat is fully cured the floor is scraped and vacuumed to remove any loose or vertical standing chips.
7. Clear Coat - NX 300 - The final step is to roll the UV stable polyaspartic clear coat.
8. Leave project broom clean

50% deposit is required to book, install and order product. Deposit balance will be collected by Our Design Consultant and final balance will be collected by Our Lead Installer, day of Installation, once it is completed.

Subtotal:	\$26,268.70
Discount:	\$2,200.00
Grand Total:	\$24,068.70

Cracks or substrate damage not covered under warranty.

You may cancel this transaction, without any penalty or obligation, within three business days from the above date.

If you cancel, any payments made by you under the contract or sale, and any negotiable instrument executed will be returned within ten business days following receipt by the seller of your cancellation notice. After 3 days, AdPro Concrete Coatings has the right to charge client up to 75% of expenses incurred for the project.

Marketing photos will be taken of your project to use for marketing purposes but all personal information will remain private.

Removal charges includes removal and discarding of tile and glue.

Due to the existence of tile on the substrate there will be a charge of \$8.00 a linear foot for any cracks that are found and \$4.75 a square foot for any pitting that is discovered.

X

Nick Shirk

X

Company Authorized Signature