

ESTIMATE



Prepared For

Yorktown Fire Station
8905 W. Smith Street
Yorktown , IN
(765) 730-3997

Sims Sealing

PO Box 12
Yorktown, IN 47396
Phone: (765) 717-4824
Email: simssealing@gmail.com
Web: Sims Sealing.com

Estimate # 169

Date 07/20/2023

Description	Rate	Quantity	Total
Sealcoating	\$0.20	29,000	\$5,800.00
Two coats of Sealmaster coal tar sealcoat with sand and additives applied by spraying application.			
Hot Rubber Crack Seal	\$0.75	1,400	\$1,050.00
Cracks to be cleaned of all debris and hot rubber crack seal applied to cracks larger than 3/8" in width. Up to 1,400 linear feet of cracks to be sealed.			
Striping	\$500.00	1	\$500.00
Re-stripe of current line markings. Add 1 handicap			
Concrete patch	\$10,400.00	1	\$10,400.00
Saw cut and removal of asphalt in area previously discussed with sub contractor Chet Burcham. Replace base and patch with concrete.			
Subtotal			\$17,750.00
Total			\$17,750.00